

Romulus Town Board Meeting

Romulus Water & Sewer District Reports

Date: March 20, 2024

To: Romulus Town Board

- ❖ Romulus Water District – February’s daily average – 42,100 gallons
- ❖ Willard Water District – February’s daily average – 21,500 gallons
- ❖ Rt. 89 Water District – February’s daily average – 5,900 gallons
- ❖ Willard WTP Total – February’s daily average – 102,000 gallons
- ❖ Willard DTC Campus – February’s unaccounted daily average – 30,000 gallons
- ❖ Water testing – all sample draws were collected and all draws are up to date in all districts.
- ❖ NYSDOH monthly reports – February’s DOH reports for all districts, were completed and sent to Seneca County Health Services
- ❖ U-DIG New York – total tickets = 15 / Regular – 15 / Emergency – 0
- ❖ Water meter change out – 3 meters
- ❖ new service truck – new service truck was finally delivered
- ❖ Willard Water Treatment Plant – we were notified by OGS that they’re going to cold close the Willard facility, working with OGS to shut down all looped water mains and all houses on facility, approximately cut and cap 20 locations, many fire hydrants will be taken out of service, filter #2 is out of service for gear box repair, backwash door was replaced and flocculator repaired, work is scheduled for next week, new fence is being installed now, had change order due to fence post placed in driveway, change order was authorized, Elevated pump #1 out of service, waiting for DOCCS to setup pump startup, working with DOCCS Albany on new electric service for Lake pump house, water tower and Water treatment plant, OGS has started to complete punch list from Health Department requirements from annual inspection - installed new curbing raw water intake - installed new RPZ backflow unit @ WTP - installed new drain lines for roof and basement – meeting is set for next week to go over filter media replacement and under drain inspection, we installed new chemical lines on PAC and polymer pumps,
- ❖ Water District Improvement Project – basement drain issues after new water main was installed, Amity Chrisman 1499 Main St., Brewer’s septic was scheduled to jet out and clean drain line, determine exact footage of damaged area, Brewers septic never showed, Brewer’s was canceled and Lagana Plumbing is scheduled to be here tomorrow morning, Wenzel spring starting date has been postponed until easements are signed

- ❖ Romulus Water District – working with Varick water department to determine water loss, also had Master Meter water meter company here to look at meter installation and data log information of Romulus meter, waiting for report back

Respectfully submitted,

Hobie

Hobie Stapleton

Water Department Superintendent